




NASA's Certification and Qualification Strategies for Additively Manufactured Hardware

Rick Russell¹, NASA Technical Fellow for Materials

Alison Park¹, Douglas Wells², Brian West², Bryan McEnerney³,
Andrew Glendening⁴, Erin Lanigan² and Will Tilson²

¹NASA Langley Research Center, ²NASA Marshall Space Flight Center, ³NASA Jet Propulsion Laboratory, ⁴NASA Goddard Spaceflight Center

Additive Manufacturing for Aerospace & Space
Hamburg, Germany
February 23, 2022



Exciting time at NASA with a lot of activities around Earth Orbit, getting ready to go to the Moon with eyes on Mars



Additive Manufacturing at NASA

- Fully embraces advantages of AM
 - Cost/lead time/part count reduction, new design and performance opportunities, rapid design-fail-fix cycles
- While fully understanding the challenges
 - Especially in delivering high value, high performance AM hardware
- NASA has dual roles
 - Drive and foster AM technology research and development in support of broad industry adoption and industrialization
 - Develop protocols for spaceflight hardware certification for access to space that can safely meet mission objectives ← Today's focus




NASA's motivation for AM Standard development




- AM parts are already being use for NASA programs in critical applications
- Human exploration of space, especially deep space, requires extreme reliability

Low Earth Paradigm



Deep Space Paradigm



250 miles vs 83,000,000+ miles
(~400 km vs 134,000,000+ km)
15-30 year life vs 50 to 100+ years
Replacement parts vs Limited replacement parts
Safe haven of earth vs no safe haven



New Agency Document Structure

MSFC-STD-3716






AMRs

MSFC-SPEC-3717



PCQRs for:
Process definition
QMPs

PCQRs for:
Equipment and facility
process control






Applicability

| Category | Technology | Materials Form | Class | | |
|----------|-------------------------|-----------------------------------|-------|---|---|
| | | | A | B | C |
| Metals | L-PBF | Metal Powder | X | X | X |
| | DED | Metal Wire | X | X | X |
| | DED | Metal Blown Powder | X | X | X |
| Polymers | L-PBF | Thermoplastic Powder | | X | X |
| | Vat Photopolymerization | Photopolymeric Thermoset Resin | | | X |
| | Material Extrusion | Thermoplastic filament | | | X |

- Adaptive technologies, where the heat input can change during the manufacturing process, are not allowed
 - e.g. Electron beam powder bed fusion (E-PBF)

Classification







Summary of Methodology



- General Requirements
 - Additive Manufacturing Control Plan (AMCP) and Quality Management System (QMS)
 - Backbone that defines and guides the engineering and production practices
- Foundational Process Control Requirements
 - Includes the requirements for AM processes that provide the basis for reliable part design and production
- Part Production Control Requirements
 - Includes design, assessment controls, plans (PPP), preproduction articles and AM production controls






AM Certification: Governing Principles

- Understanding and Appreciation of the AM process
- Integration across disciplines and throughout the process
- Discipline to define and follow the plan


- Have a plan
- Integrate a Quality Management System (QMS)
- Build a foundation
 - Equipment and Facility
 - Training
 - Process and machine qualification
 - Material Properties / SPC
- Plan each Part
 - Design, classification, Pre-production articles
 - Qualify and lock the part production process
- Produce to the plan – Stick to the plan





QMP: Qualified Material Process


- Begins as a Candidate QMP
- Defines aspects of the basic, part agnostic, fixed AM process:
 - Feedstock Controls
 - What you are building with
 - Fusion Process
 - How a machine operates
 - Thermal Process
 - Control what evolves your material state
- Qualification of the Candidate Material Process
 - Establishes a QMP: Qualified Material Process
 - Requirements vary based on classification
- Enabling Concept
 - Machine qualification and re-qualification, *monitored by...*
 - Process control metrics, SPC, *all feeding into...*
 - Design values



- AM machine and process are indelibly linked:
 - Step 1: Define a candidate process
 - Step 2: Qualify the candidate process to well-defined metrics



The QMP becomes the Foundation!






Material Properties




The Material Property Suite (MPS) consists of four inter-related entities:

1. Data Repository
2. Design Values
3. Process Control Reference Distribution (PCRD)
4. SPC acceptance criteria for witness testing




Material Properties – PCRDR



Process Control Reference Distribution

- Statistically describes nominal witness behavior of a machine
- Utilizes all appropriate sources of *witness coupon data* in Repository
- Used to set acceptance criteria for witness tests






Material Properties – SPC



Statistical process controls are important in sustaining certification rationale

- *Statistical equivalency evaluations* substantiate design values and process stability build-to-build
 - a) Process qualification
 - b) Witness testing
 - c) Integration to existing material data sets
 - d) Pre-production article evaluations
- Equivalency of material performance is an anchor to the structural integrity rationale for additively manufactured parts



The dark and scary place most manufacturers are NOT used to operating....






Material Properties Suite






Statistical Process Control Acceptance Criteria

- Derived from PCRD
- Acceptance criteria for witness tests




SPC Acceptance
Criteria for
Witness Testing





Material Properties Suite – PCR and SPC Criteria

- Witness test acceptance is **not** intended to be based upon design values or “specification minimums”
- Acceptance is based on witness tests reflecting properties in the MPS used to develop design values
- Suggested approach
 - Acceptance range on mean value
 - Acceptance range on variability (e.g., standard deviation)
 - Limit on lowest single value






Foundation Complete!!

A basis to begin designing AM parts with certification intent is feasible once the foundation is laid.

Foundation is now ready to support AM part development in an environment with suitable rigor to establish certification.






AM Part Production

1. Follow the plan, always, with no short-cuts
2. Do not change a Qualified Part Process without re-qualification
3. Efficiency in process monitoring is critical to minimize the inevitable disruption
 - Witness tests can take considerable time to complete
 - Track the performance of each machine using all available metrics by control chart
 - In-process monitoring may provide early warning of changes in machine performance
4. Emphasize the importance of inspection for every part
 - Not just NDE, but visual inspection of as-built conditions
 - Watch for changes in part appearance – colors, support structure issues, witness lines/shifts
5. Consider systemic implications for all non-conformances



Key AM Qualification Concepts



Part reliability rationale comes from the sum of both in-process and post-process controls, weakness in one must be compensated in the other



Fracture Control Framework for AM Parts

- Fracture control is reliant on understanding the design, analysis, testing, inspection and tracking of hardware.
 - The adaptation of state-of-the-art AM technologies introduces new and unique challenges
 - e.g. Multiple lasers and adaptive technologies
 - For AM applications the application of conventional NDE techniques is questionable
 - There is a need to produce alternate approaches through the adaptation of a Probabilistic Damage Tolerance Approach (PDTA)
 - Computational modeling for AM
 - Understanding the “Effects of defects”
 - In-situ monitoring and inspection
- These items
MUST
Work
together not
separate



Computational Modeling of AM


- Two aspects of qualification and certification to consider:
 1. Design Certification
 - Demonstration that design meets all the requirements of the defined mission
 2. Hardware Certification
 - Demonstration that the hardware meets all the requirements of the certified design
- Opportunities for computationally-assisted qualification and certification
 - Focus primarily on augmenting the existing qualification and certification processes, NOT replacing them
 - Such methods fit into current NASA AM requirements
 - Such tools will require verification and validation
 - Leverage government-industry partnerships



Computational Modeling Opportunities

Design Cert

Hardware Cert







Effects of Defects



- **Flaw** – an imperfection or discontinuity that may be detectable by nondestructive testing and is not necessarily rejectable.
- **Defects** – one or more flaws whose aggregate size, shape, orientation, location, or properties do not meet specified acceptance criteria and are rejectable.



Flaws in AM fall into two categories


1. **Inherent flaws** – Flaws that are representative of the characterized nominal operation of a qualified AM process.
2. **Process Escape flaws** – Flaws that are not representative of the characterized nominal operation of a qualified AM process.



Effects of Defects



- Current NESC Assessment
 - Phase 1: Understanding inherent defects
 - Catalogue and understand the physical cause and characteristics of defects in AM processes through expert solicitation and literature review.
 - Investigate methodologies to characterize the rates of occurrence as a function of size for inherent defects for a given AM process, including operations at the defined edge of the process window.
 - Investigate methods of evaluating the inherent defect state throughout the AM process window through parameter design of experiments or geometry-based process challenge builds.





Effects of Defects



- Future planned work
 - Phase 2: Using process controls to control inherent defect populations
 - Determine the feasibility of using process controls (and limitations thereof) to govern the population of inherent defects in AM hardware through the controls of NASA-STD-6030, in-situ monitoring, or other means.
 - Determine the feasibility and limitations of incorporating the inherent defect population into fatigue design values.
 - Phase 3: Understanding Rogue defects
 - Determine feasibility of Process Failure Modes and Effects Analysis (P-FMEA) to understand the characteristics and occurrence likelihood of potential rogue AM defects.
 - Determine the feasibility of using process controls to limit the population of rogue defects in AM hardware through the controls of NASA-STD-6030, in-situ monitoring, or other means.
 - Map the physical cause of rogue defects for a given AM machine/process against available/potential in-situ monitoring techniques to evaluate the ability to preclude the defects or bound their size during the process.
 - Investigate practical methods to apply the above knowledge of defect state to practical PDTA to inform failure risk.

Initial effort
already started
in partnership
with the ASTM
Center of
Excellence



In-situ Monitoring

- NASA-STD-6030 requires
 - Quantitative NDE for class A parts
 - NDE for process control for class B parts
 - In-situ monitoring must be qualified in manner analogous to other NDE techniques
- Two main functions of in-situ process monitoring:
 - Process Control
 - Real-time warnings of build problems
 - Check for process drift
 - Monitor effects of parameter changes
 - Part Quality
 - Quantitative analysis
 - Requires correlations between indications, physics of the process and actual defects
 - Need to know probability of detection

} Must meet requirements of NASA-STD-5009



In-situ Monitoring

- Challenges to using in-situ monitoring:
 - Indirect defect observations will require an understanding of the physics
 - Current certification approach requires a locked process
 - For real-time changes a new approach is needed
 - Current certification approach does not accommodate the use of adaptive systems
 - Creates two issues for verification
 1. Verify the sensor performance, algorithm and machine response (control system)
 2. Verify the physics – does controlling this parameter result in a good part?



Conclusions

1. Certification rationale is most heavily rooted in the foundational controls
2. Part Planning must confirm the foundation produces a good part consistently
3. Part production follows a fixed process with statistical process controls
4. Going forward NASA must develop a Fracture Control Framework for AM Parts which includes the adaptation of a Probabilistic Damage Tolerance Approach (PDTA)
 - Computational modeling for AM
 - Understanding the “Effects of defects”
 - In-situ monitoring and inspection